

कार्यालय, नगर पालिक निगम, भिलाई

निविदा सूचना

भिलाई दिनांक 22/12/2022

क्रमांक / परिशा./न.नि./2022/546

आयुक्त नगर पालिक निगम भिलाई की ओर से विभागीय कार्य हेतु पंजीकृत ठेकेदारों से से मुहरबंद तिकाफा दिनांक 06/01/2023 को साथ 05.00 बजे तक आमंत्रित की जाती है। प्राप्त निविदायें दिनांक 09/01/2023 को 11:00 बजे उपस्थित निविदाकारों अथवा उनके अधिकृत प्रतिनिधियों के सम्मक्ष होती जावेंगी। अवकाश के अन्तिम में अगले कार्य दिवस निविदा खाली जावेंगी। निविदा में भाग लेने हेतु दिनांक 04/01/2023 तक 05:30 बजे तक निविदा फॉर्म आवेदन के साथ फॉर्म की जा सकती है।

क्र.	कार्य का नाम	निविदा लागत	घरोहर राशि	निविदा प्रपत्र का मूल्य	समायावधि	निविदा फॉर्म
1	नगर पालिक निगम, भिलाई के जॉन क्रमांक 05 में स्थायीकरण मार्गों का पेव रिपेयर कार्य।	4.73 लाख	5000.00	750.00	60 दिन	फॉर्म "A"

शियम एवं शर्तें- 1. सवार्त निविदा स्वीकार नहीं की जावेंगी। 2. निविदा स्वीड पोस्ट एवं रोजरटर्ड डाक से स्वीकार किये जावेंगी। 3. घरोहर राशि EDR कार्यपालन अधिकारता के नाम से तिकाफा क में प्रस्तुत करना होगा तथा निविदा दर तिकाफा या में प्रस्तुत करना होगा। 4. दरें सामल कर सहित देना होगा। 5. सम्पूर्ण निविदा अथवा किसी भी अंश को स्वीकृत करने अथवा न करने का अधिकार आयुक्त नगर पालिक निगम भिलाई के पास सुरक्षित रहेगा। 6. सामल के आदेश दिनांक 19.01.2012 के अनुसार अनुमानित लागत से 10 प्रतिशत कम निविदा दर होने पर सामल निविदाकार को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत के अंतर की राशि के समस्तुत्प परकार्तन गारंटी के रूप में एक डी.आर. जमा करना होगा। 7. किसी भी विवाद की स्थिति में आयुक्त नगर पालिक निगम भिलाई का निर्णय अन्तिम एवं मान्य होगा। 8. कार्य के संबंध में विस्तृत शियम एवं शर्तों की जानकारी कार्यालयीन अवधि कार्यालय अभियंता भवन संचारण से प्राप्त की जा सकती है। 9. निविदा नगर पालिक निगम भिलाई की वेबसाइट www.phillainmpn.org.in अथवा संचालनालय की वेबसाइट www.urd.gov.in से भी देखी जा सकती है।

कार्यपालन अभियंता
नगर पालिक निगम
भिलाई


OFFICE OF THE MUNICIPAL CORPORATION OF BHILAI
ZONE-05 SECTOR 06


NIT

Detailed Estimate for repairing of BT road from MIG-1,745 & MIG-2,37 and in hudco area -

(Based on PWD Road SOR Wef from Dated 01-01-2015)

S. No.	SOR Ref	DESCRIPTION	QTY	UNIT
1	2	3	8	9
1	2.5 A	Dismantling of flexible pavements and disposal of dismantled materials up to a lead of 1000 meters, stacking serviceable and unserviceable materials separately and as per relevant clauses of section-200. Bituminous courses	36	cum
2	5.1 (i)	Prime coat (Providing and applying primer coat with oil based bitumen emulsion (SS-1, grade confirming to IS:8887) on prepared surface of granular Base including clearing of road surface and spraying primer using mechanical means as per clause 502. on WBM/WMM surface @0.85 Kg/sqm	360	sqm
3	5.4 B (ii)	Dense Bituminous Macadam (Providing and laying dense bituminous macadam with minimum 40-60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder @ 4.0 to 4.5% by weight of total mix of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No.505 complete in all respects.)With mechanical paver finisher for Grading-II(26.5 mm nominal size bitumen content 4.50%)	27	cum
4	5.2 (i)	Tack coat Providing and applying tack coat with bitumen emulsion (RS-1, grade confirming to IS:8887) using emulsion pressure distributor on the prepared bituminous/granular surface cleaned with mechanical broom and as per clause 503. Bituminous surface @ 0.25 kg /Sqm	400	sqm
5	5.5 B (iii)	Bituminous Concrete (Providing and laying bituminous concrete with minimum 40-60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.0 to 6.0% by weight of total mix of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects)With mechanical paver finisher for Grading II (13.2 mm nominal size) with bitumen 6.0%	20	cum
6	8.13	Road Marking with Hot Applied Thermoplastic Compound with Reflectorizing Glass Beads on Bituminous Surface (Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorizing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35-1997. The finished surface to be level, uniform and free from streaks and holes.)	20	sqm


Asst. Engineer
Municipal Corporation
Bhilai


Sub-Engineer
Municipal Corporation
Bhilai

- After the Construction of B.T. Road a Period of 01 year shall be kept as performance guarantee period.
- The contractor shall also be responsible for performance of work carried out by him for a period of 12 month beyond the completion of work for which performance security has to be furnished by him @ 5% (five percent) of amount of contract. For this purpose contractor has to submit to the department a Bank Guarantee of 5% amount of the value of work done on every running and final bill payable to him. If contractor fails to submit bank guarantee of 5% amount of the gross bill, then 5% amount of bill shall be deducted from his running and final bill payment. However, the contractor can get refund of such performance cash security amount deducted if he submits appropriate bank guarantee valid for the period as stated above or 12 month after actual completion.


[Handwritten signature]

[Handwritten signature]

[Handwritten signature]

MUNICIPAL CORPORATION BHILAI
SPECIAL CONDITION FOR PATCH WORK ON BR ROAD

- 1- For construction of BT road partly or fully, it is essential that bidders must have their own hot mix plant and paver finishing machine. The contractor should submit necessary documents of above described machineries and plants
- 2- Hot mix plant 40-60 TPN self attested Certificate.


Executive Engineer
Municipal Corporation
Bhilai