

## कार्यालय, नगर पालिक निगम, भिलाई निविदा सूचना


क्र/लो.क.वि./जोन-1/34

भिलाई, दिनांक 2/12/22

आयुक्त नगर पालिक निगम भिलाई की ओर से लोक निर्माण विभाग मे ई-रजिस्ट्रेशन में पंजीकृत ठेकेदारों से लोक निर्माण विभाग के भवन एस.ओ.आर. दिनांक 01.01.2015 एवं सड़क एस.ओ.आर. दिनांक 01.01.2015 से लागू एवं अद्यतन संशोधन के आधार पर कम/अधिक एवं आयटम दर पर निम्नांकित कार्य दिनांक 29.12.2022 को सायं 5.30 बजे तक मुहरबंद निविदा आमंत्रित की जाती है। प्राप्त निविदा दिनांक 30.12.2022 को प्रातः 11.00 बजे खोली जावेगी। निविदा प्रपत्र हेतु आवेदन दिनांक 22.12.2022 को सायं 5:30 बजे तक निर्धारित राशि के साथ आवेदन स्वीकार किये जावेगा।

क्र.	कार्य का नाम	निविदा लागत (लाख में)	धरोहर राशि	निविदा प्रपत्र का मूल्य	समयावधि	ठेकेदार की श्रेणी
1.	पार्षद निधि वर्ष 2022-23 से वार्ड-01 जुनवानी सतनामी पारा पुन्नी बाई घर से मेन रोड तक सी.सी. रोड एवं आर.सी.सी. नाली निर्माण कार्य।	4.50	4500.00	750.00	60 दिन	द एवं प्रवर
2.	पार्षद निधि से वर्ष 2021-22 से वार्ड-01 जुनवानी सतनामी पारा शिव मंदिर से प्रेमलाल बारले के घर तक सी.सी.रोड एवं आर.सी.सी. नाली निर्माण कार्य।	3.98	4000.00	750.00	60 दिन	द एवं प्रवर
3	वार्ड-09 गौतम नगर सतनामी पारा में सी.सी.रोड एवं नाली निर्माण कार्य।	4.00	4000.00	750.00	60 दिन	द एवं प्रवर
4.	वार्ड-13 पुरानी बस्ती कोहका में सार्वजनिक चबूतरा निर्माण कार्य।	3.00	3000.00	750.00	90 दिन	द एवं प्रवर
5.	वार्ड-01 स्वामी आत्मानंद अंग्रेजी माध्यम शास.उ.मा.शाला खम्हरिया जुनवानी भिलाई में वाटर कूलर कार्य।	2.00	2000.00	300	45 दिन	द एवं प्रवर

एवं शर्तें:- 1. सशर्त निविदा स्वीकार नहीं की जावेगी। 2. निविदा स्पीड पोस्ट अथवा रजिस्टर्ड डाक से स्वीकार किये जावेंगे। 3. धरोहर राशि कार्यपालन अभियंता /जोन आयुक्त, नगर पालिक निगम, भिलाई एवं संबंधित ठेकेदार के नाम से तथा प्रत्येक कार्य के लिये जीवित ठेकेदारी ई-पंजीयन, पेनकार्ड, आयकर, जीवित बैंक सालवेंसी प्रमाण, GST पंजीयन पत्र की सत्यापित प्रति लिफाफा "क" में प्रस्तुत करना है, एवं निविदा प्रपत्र दर सहित लिफाफा "ख" में प्रस्तुत करना होगा। 4. कर्मकार कल्याण उपकर अधिनियम लागू होगी। 5. सम्पूर्ण निविदा अथवा किसी भी अंश को स्वीकृत करने अथवा न करने का अधिकार निगम के पास सुरक्षित रहेगा। 6. नगर निगम की वाहनों से निर्माण कार्य हेतु पानी लेने पर देयक से 1 % राशि की कटौती की जावेगी, किन्तु निगम वाहनों से जल उपलब्ध कराने हेतु बाध्य नहीं रहेगा। निगम क्षेत्र के स्रोतों से स्वयं के वाहनों से पानी लेने पर 0.5 % की कटौती की जावेगी। 7. ठेकेदार द्वारा निविदा में अंको एवं शब्दो दोनों में स्पष्ट रूप से दरे प्रस्तुत करें नही किये जाने पर निविदा फार्म निरस्त किया जावेगा। 8. शासन के आदेश क्रमांक 19 दिनांक 04.06.2016 के सफल निविदाकार की निविदा दर निविदा राशि के 90% से कम होने की स्थिति में अंतर की राशि एफ.डी.आर. के रूप में संविदा के पूर्व जमा करना होगा। 9. शासन के निर्देशानुसार श्रमिको से संबंधित कार्यो हेतु श्रमिकों का पी.एफ. कटौती किया जाना हैं तथा बैंको में खाता खोलकर सीधे उनके बैंक खाते में श्रमायुक्त द्वारा स्वीकृत दरों के अनुरूप प्रतिमाह राशि जमा किया जाना है। 10. प्रस्तुत दस्तावेज असत्य पाये जाने पर पंजीयन निरस्त कर, काली सूची मे दर्ज करने की कार्यवाही की जावेगी। 11. यदि निगम द्वारा निर्धारित निविदा प्राप्ति की अंतिम तिथि/निविदा खोलने की तिथि को किसी अपरिहार्य कारणवश अवकाश घोषित होता है तो ऐसी स्थिति मे अंतिम तिथि/खोलने की तिथि आगामी कार्य दिवस को माना जायेगा। 12. प्रत्येक कार्य के लिए पृथक-पृथक धरोहर राशि जमा करें एवं समयोजन की कार्यवाही नही होगी। 13. शासन के निर्देशानुसार G.S.T. एवं अन्य कर सम्मिलित रहेगा। 14. निविदा में भाग लेने वाले इच्छुक एजेंसी प्रत्येक कार्य के लिए राशि रु. 100.00 स्टाम्प एफिडेविट संलग्न करना अनिवार्य होगा। 15. किसी भी विवाद स्थिति में आयुक्त/जोन आयुक्त नगर पालिक निगम, भिलाई का निर्णय अंतिम एवं मान्य होगा। विस्तृत जानकारी कार्यालयीन समय एवं तिथि मे कार्यालय नगर पालिक निगम भिलाई नेहरु नगर जोन-01, नगर निगम भिलाई की वेबसाईट [www.bhilainagarnigam.com](http://www.bhilainagarnigam.com) अथवा संचालनालय की वेबसाईट [www.uad.cg.gov.in](http://www.uad.cg.gov.in) एवं चीप्स की वेबसाईड [eproc.cgstate.gov.in](http://eproc.cgstate.gov.in) से देखी जा सकती है।

  
जोन आयुक्त  
जोन-01  
नगर पालिक निगम,  
भिलाई


# MUNICIPAL CORPORATION BHILAI (C.G.)


## NIT


कार्य का नाम :-वार्ड-01 जुनवानी सतनामी पारा पुन्नी बाई घर से मेन रोड तक सी.सी. रोड एवं आर.सी.सी. नाली निर्माण कार्य।

Pwd Building / Road Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	30.72	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	5.76	Cum
3	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	166.40	Sqm
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	10.08	Cum
5	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	5.76	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete.Thermo-Mechanically treated bars.	705.60	KG
7	Carriage by mechanical transport for 5 km lead.	30.72	Cum
8	Providing and laying Cement Concrete for plain concrete/reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C.M. 30	73.80	Cum

  
**Executive Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Asstt. Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Sub. Engineer**  
Municipal Corporatio  
Bhilai (C.G)


**MUNICIPAL CORPORATION BHILAI (C.G.)**  
**NIT**


कार्य का नाम :-वार्ड-01 जुनवानी सतनामी पारा शिव मंदिर से प्रेमलाल बारले के घर तक सी.सी. रोड एवं आर. सी.सी. नाली निर्माण कार्य।

PwD Building / Road Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	25.00	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	25.00	Cum
3	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	130.00	Sqm
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3	7.88	Cum
5	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	4.50	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	551.25	KG
7	Carriage by mechanical transport for 5 km lead.	24.00	Cum
8	Providing and laying Cement Concrete for plain concrete/reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C.M.-20	68.40	Cum

  
**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Sub. Engineer**  
**Municipal Corporatio**  
**Bhilai (C.G)**

# MUNICIPAL CORPORATION BHILAI (C.G.)

## NIT


कार्य का नाम :- वार्ड-09 गौतम नगर सतनामी पारा में सी.सी. रोड एवं नाली निर्माण कार्य।

Pwd Building/Road Sor 01.01.2015


S.No.	Description and details of work	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	48.32	Cum
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	61.90	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	8.50	Cum
4	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	201.52	Sqm
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	19.97	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	620.10	KG
7	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	11.90	Cum
8	Carriage by mechanical transport for 5 km lead.	50.72	Cum
9	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	0.48	Cum
10	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	2.07	Cum
11	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.63	Cum
12	Providing and laying Cement Concrete for plain concrete/reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C.M.-25	45.00	Cum



**Executive Engineer**  
Municipal Corporation  
Bhilai (C.G)



**Asstt. Engineer**  
Municipal Corporation  
Bhilai (C.G)



**Sub. Engineer**  
Municipal Corporation  
Bhilai (C.G)

# MUNICIPAL CORPORATION BHILAI (C.G.)

## NIT

कार्य का नाम :- वार्ड-13 पुरानी बस्ती कोहका में सार्वजनिक चबूतरा निर्माण कार्य।


Pwd Building Sor 01.01.2015 & Electric Sor 01.06.2020

S.No.	Description and details of work	Qty.	Unit
1	Demolishing stone rubble masonry including arches, stacking of serviceable material and disposal of unserviceable material within 50 Metres lead.	2.40	Cum
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	25.61	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.03	Cum
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	16.123	Cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars	1612.25	Kg
6	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
	(A) Foundations, footings, base of columns and plinth beam in any shape and size.	21.66	Sqm
	(B) Columns. Pillars. Piers and likes rectangular or square in shape	23.10	Sqm
	(C) Beams, lintels, cantilevers & walls	8.84	Sqm
	(C) Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	58.26	Sqm
7	Providing and filling in plinth with sand/Crusher dust and hard moorum under floor, including ----- cost of all labour, materials, T & P etc. complete required for the work.	21.23	Cum
8	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in :Cement Mortar 1:6	2.65	Cum
9	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form work.	0.22	Cum
10	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in :Cement Mortar 1:6 Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	3.83	Cum
11	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	44.88	Sqm
12	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	19.14	Sqm
13	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	19.14	Sqm

14	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 50 mm thick	38.38	Sqm
15	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm	43.29	Sqm
16	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	20.16	Sqm
17	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	19.14	Sqm
18	Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. On new work (two or more coats)	44.88	Sqm



**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**



**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**



**Sub. Engineer**  
**Municipal Corporatio**  
**Bhilai (C.G)**


# MUNICIPAL CORPORATION BHILAI (C.G.)


## NIT


कार्य का नाम :- वार्ड-01 स्वामी आत्मानंद अंग्रेजी माध्यम शास.उ.मा.शाला खम्हरिया जुनवानी भिलाई में वाटर कूलर कार्य।

(As Per PWD Building Sor 01.01.2015& Electric Sor 01.07.2015)

S.No.	Description and details of work	Qty.	Unit
1	Wiring for light/ fan/ exhaust fan / call bell point with 3x1.5 sqmm FRLS PVC insulated stranded copper conductor wire for phase, neutral and earth in surface FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) with 5/6 amp modular switch, modular base and cover plate, suitable size G.I. box as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)	5.00	Point
	Short Point	5.00	Point
	Medium Point	5.00	Point
	Long Point		
2	Supplying, installation, testing and commissioning of following size drinking water cooler storage type ISI marked, eco friendly non CFC refrigerant, water tank and cooler cabinet sheet material- stainless steel {grade AISI 304} with thickness >= 0.8 mm, with PUF insulation including all accessories connection etc complete as per specification. 150/150 Ltrs/hr	2.00	Nos
3	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, wire in surface FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) etc as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5) 3 X 2.5 sq. mm in 20mm conduit	75.00	Metre
4	Supplying, installation, testing and commissioning of following capacity of RO purification system with UF/UV/TDS controler and UV lamp {IS 14724 Ultra violet disinfection} and minimum three stage purification, automatic on/off, output water conforming standard IS 10500 with inbuild storage tank including all accessories connection etc complete as per specification. 50 Ltrs/hr output capacity	2.00	Nos
5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	1.92	Cum
6	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	3.24	Cum
7	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	8.64	Sqm
8	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.296	Cum
9	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	8.64	Sqm
10	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sam)	8.64	Sqm

  
**Executive Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Asstt. Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Sub. Engineer**  
Municipal Corporatio  
Bhilai (C.G)