MUNICIPAL CORPORATION BHILAI (C.G.) NIT

कार्य का नाम :-वार्ड-01 जुनवानी सतनामी पारा पुन्नी बाई घर से मेन रोड तक सी.सी. रोड एवं आर.सी.सी. नाली निर्माण कार्य।

Pwd Building / Road Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	30.72	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	5.76	Cum
3	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: a)Foundations, footings; base of columns and plinth beam in any shape and size	166.40	Sqm
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	10.08	Cum
5	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	5.76	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	705.60	KG
7	Carriage by mechanical transport for 5 km lead.	30.72	Cum
8	Providing and laying Cement Concrete for plain concrete/reinforced concrete i/c form work, shuttering copmlete in as per drawings and specifications. (For Village roads) P.C.C.M30	73.80	Cum

Executive Engineer Municipal Corporation Bhilai (C.G)

Asstt. Engineer **Municipal Corporation** Bhilai (C.G)

Sub. Engineer **Municipal Corporatio** Bhilai (C.G)