



**MUNICIPAL CORPORATION BHILAI (C.G.)**  
**NIT**


कार्य का नाम :-वार्ड-01 जुनवानी सतनामी पारा शिव मंदिर से प्रेमलाल बारले के घर तक सी.सी. रोड एवं आर. सी.सी. नाली निर्माण कार्य।

PwD Building / Road Sor 01.01.2015

| S.No. | Description and details of work  | Qty.   | Unit |
|-------|--|--------|------|
| 1     | Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.  | 25.00  | Cum  |
| 2     | Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) | 25.00  | Cum  |
| 3     | Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size              | 130.00 | Sqm  |
| 4     | Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3  | 7.88   | Cum  |
| 5     | Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.     | 4.50   | Cum  |
| 6     | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.                               | 551.25 | KG   |
| 7     | Carriage by mechanical transport for 5 km lead.  | 24.00  | Cum  |
| 8     | Providing and laying Cement Concrete for plain concrete/reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads)<br>P.C.C.M.-20   | 68.40  | Cum  |

  
**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Sub. Engineer**  
**Municipal Corporatio**  
**Bhilai (C.G)**