NAGAR PALIK NIGAM, BHILAI

NIT

वार्ड क्र.—19 राजीव नगर गुरूनानक नगर, आजाद चौक, कारगिल चौक, दुर्गा टिम्बर के पीछे एवं साहू पारा में पुलिया संधारण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)

CNIC	(As per P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)		
S.NO	FARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose		
	including disposal of excavated stuff upto 1.5 m liftand lead upto 50m (at least 5m away from		
	the excavated area), including dressing and leveling of pits. In all types of soils.		,
		36.90	CUM
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using		
	concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		3.69	CUM
4	Providing and fixing form work including centring, shuttering, strutting, staging, propping		
	bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases		
	of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.		
		150.90	SQM
	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate		
	using concrete mixer in all works upto floor five level excluding cost of reinforcement and		
	form work .1:11/2:3 (1 cement : 11/2 coarse sand : 3 graded stone aggregate 20mm nominal size).		
		27.06	CUM
5	Providing and placing in position reinforcement for R.C.C. work including straightening,		
	cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415		
		2706.00	KG
6	Carriage by mechanical transport upto 5 km lead: Earth	18.45	CUM
	· ·		
	ASSTT.ENGINEER SUB EI	NGINEER	

