## MUNICIPAL CORPORATION OF BHILAI

## NIT

## कार्य का नाम -वार्ड क्रं० 56 सेक्टर 02 सड़क 16 स्थित संकट मौचन हनुमान मंदिर के समीप मंच निर्माण (संधारण) कार्य।

(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020)

	(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2		
S.N.	PARTICULERS OF ITEMS	Quanti	ty UO
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), includingdressing and leveling of pits. In all types of soils.	48.00	Cur
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	8.00	Cun
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	12.00	Cum
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating eachdeposited layer by ramming and watering, including dressing etc. complete.	3.00	Cum
•	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:Cement Mortar 1:6 (1 cement : 6 coarse sand)	4.32	Cum
6	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:Cement Mortar 1:6 (1 cement : 6 coarse sand)Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	7.20	Cum
7	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand	32.00	Sqm
8	Providing and making 15mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand	25.60	Sqm
9 5	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to giveprotective and decorative finish including cleaning washing of surface etc. complete with:On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and neluding priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	74.50	Sqm
	White washing with whiting to give an even shade. On new work (Three or more coats)	57.60	Sqm
12	Distempering with acrylic washable distemper to give an even shade. On new work (Two or more coats)	57.60	Sqm
13 :	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	80.00	Sqm
14 5	Providing stainless steel railing/grill made of S.S. flats, hollow S.S. pipe or square/rectangular ections of approved design fixing in stair case, balcony or other places with metal fasteners and tainless steel bolts etc complete.SS Grade 304	200.00	KG
15 F	airting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	80.00	Sqm

कार्यपालन अभियन्ता नगर पालिक निगग, मिलाई र्वसहायक अभियन्ता नगर पालिक निगम, मिलाई उप श्रीमेंबीता नगर पालिक निगम, मिलाई