


6


MUNICIPAL CORPORATION BHILAI
NIT


कार्य का नाम :- वार्ड क्रमांक 34 शिवशक्ति कॉलोनी रोड डामरीकरण कार्य।

Estimate Based on SOR for ROAD works w.e.f 01/01/2015

S.NO.	PARTICULARS OF ITEMS	QTY.	UNIT
1	Scarifying existing bituminous surface to a depth of 50 mm (Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material with in all lifts and lead up to 1000 meters) as per clause 305.4.3.	800.00	sqm
2	Tack coat Providing and applying tack coat with bitumen emulsion (RS-1, grade confirming to S:8887) using emulsion pressure distributor on the prepared bituminous/granular surface cleaned with mechanical broom and as per clause 503. (i) Bituminous surface @ 0.25 kg /Sqm	800.00	sqm
3	Providing and laying leveling course / profile corrective course with bituminous macadam With minimum 40-60 TPH capacity hot mix plant using crushed aggregates of Grading-1 premixed with bituminous binder @ 3.1% transported to site and laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clause-501.6 and 501.7 to achieve the desired compaction complete in all respect and as per relevant clause section 500. With sensor paver finisher	60.00	cum
4	Bituminous Macadam (Providing and laying bituminous macadam as per clause 504 with mixed prepared in minimum 40-60 TPH capacity hot mix plant using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction) With sensor paver finisher for Grading-I (40 mm nominal maximum size, bitumen content 3.30%)	83.20	cum
5	Close Graded Premix Surfacing/Mixed Seal Surfacing (Mechanical means using minimum 40-60 TPH capacity of HMP. Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness using bitumen to the required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a Smooth wheeled roller 8-10 tonne capacity, and finishing to required level and grade, complete as per clause 508) II- With mechanical paver finisher Type B (13.2 mm to 0.09 mm size aggregates)	800.00	Sqm


कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई


सहायक अभियन्ता
नगर पालिक निगम, भिलाई


उप अभियन्ता
नगर पालिक निगम, भिलाई

छत्तीसगढ़ शासन
लोक निर्माण विभाग
मंत्रालय
महानदी भवन, नवा रायपुर अटल नगर, जिला-रायपुर, 492002

-: आदेश :-

नवा रायपुर अटल नगर, दिनांक 12/12/2019

क्रमांक एफ 21-5/टी/19/2012/निविदा- राज्य शासन एतद् द्वारा वर्तमान में प्रचलित विस्तृत N.I.T. (Appendix 2.10) के Annexure- "G", Special Conditions of N.I.T. की कंडिका 4 (Performance Guarantee) में आंशिक संशोधन करते हुए बिन्दु क्रमांक (i), (iv), (v) में निम्नानुसार संशोधन करता है:-

(i) The contractor shall also be responsible for performance of work carried out by him for a period of 60 (Sixty) month beyond the completion of work for which performance security has to be furnished by him @5%(five percent) of amount of contract. For this purpose contractor has to submit to the department a Bank Guarantee of 5% amount of the value of work done on every running and final bill payable to him. If contractor fails to submit bank guarantee of 5% amount of the gross bill, then 5% amount of bill shall be deducted from his running and final bill payment. However, the contractor can get refund of such performance cash security amount deducted if he submits appropriate bank guarantee valid for the period as stated above or 60 (Sixty) month after actual completion.

If require, the Executive Engineer shall ask the contractor to extend the validity period of the Bank Guarantee(s) for such period which he considers it proper and the contractor shall extend the validity period of such Bank Guarantee accordingly. If the contractor fails to extend the period accordingly, the Executive Engineer shall encash the B.G. before the expiry of the validity period.

(iv) After three years of completion of construction, 50% (fifty percent) of available performance Bank guarantee shall be returned to the contractor subject to the satisfaction of the Executive Engineer.

(v) Remaining performance Bank Guarantee as would be remaining (after recovery all cost plus 15% (Fifteen percent) for rectification of defects, if done by the department or through other agency) shall be returned after 60 (Sixty) months of completion. The performance guarantee will be in addition to the normal security to be deducted as per clause 1 of agreement for the execution of contract.

कंडिका 4 (Performance Guarantee) के शेष बिन्दु यथावत रहेंगे। उक्त आदेश जारी दिनांक से प्रभावशील होगा।

छत्तीसगढ़ के राज्यपाल के नाम से
तथा आदेशानुसार

(जे.एम.लुलु) 12.12.19
उप सचिव

छत्तीसगढ़ शासन, लोक निर्माण विभाग
नवा रायपुर अटल नगर, दिनांक 12/12/2019

पृ. क्र.एफ.21-5/टी/19/2012/निविदा
प्रतिलिपि:-

1. निज सचिव, माननीय मंत्री जी, छ.ग. शासन, लो.नि.वि. मंत्रालय, नवा रायपुर अटल नगर की ओर उनके कार्यालयीन जावक क्र. 879, दिनांक 09.12.2019 के सादर सूचनार्थ सम्प्रेषित।
 2. प्रमुख अभियंता, लोक निर्माण विभाग, निर्माण भवन, नवा रायपुर अटल नगर,
 3. समस्त मुख्य अभियंता, लो.नि.वि. परिक्षेत्र
 4. समस्त अधीक्षण अभियंता, लो.नि.वि. मंडल
 5. समस्त कार्यपालन अभियंता, लो.नि.वि. संभाग
- की ओर सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

उप सचिव

छत्तीसगढ़ शासन लोक निर्माण विभाग