

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 51 अन्नपुरा भवन का संधारण कार्य। (पार्षद निधि)


& NON SOR
(AS PER PWD BUILDING SOR 01.01.2015)

SN	PARTICULARS OF ITEMS	QTY.	UNIT
1	Dismantling lime/ cement plaster or skirting at any height raking out joints and cleaning the surface for plaster including disposal of rubbish within 50 metres lead.	80.34	Sqm
2	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 40 mm thick	118.80	Sqm
3	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	706.20	Sqm
4	Distemping with acrylic washable distemper to give an even shade. On new work (Two or more coats)	706.20	Sqm
5	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	333.78	Sqm
6	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	53.04	Sqm
7	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Plain/ normal coloured precast interlock concrete block	96.20	Sqm
8	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.16	Cum
9	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	19.24	Cum
10	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	Litre
11	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4 mm thickness	12.48	Sqm
12	Add 20% For Electrification, Sanitary & Water Supply	58266.00	LS

SN	PARTICULARS OF ITEMS	QTY.	UNIT
13	NON SOR ITEM Providing & Supplying Nilkamal CHR2060 Plastic Mid Back with Arm Chair Chairs for Home, Dining Room, Bedroom, Kitchen, Living Room, Office and Outdoor & Garden Dust Free 100%Polypropylene Stackable Chairs	62	Each
14	NON SOR ITEM Providing & Supplying of Engineered Wood Study Table and Office Desk. Size - 57D x 116W x 73H Centimeters	2	Each



Executive Engineer
Municipal Corporation
Bhilai



Assistant Engineer
Municipal Corporation
Bhilai



Sub Engineer
Municipal Corporation
Bhilai