



NAGAR PALIK NIGAM BHILAI

NIT

वार्ड क्र.-23 घासीदास नगर समता चौक के आसपास सीमेंटीकरण एवं नाली निर्माण कार्य।

(As per P.W.D BUILDING/ROAD S.O.R. W.E.F. 01.01.2015)

S.N	PARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains of m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	9.00	cum
2	Providing and laying nominal mix cement concrete with crushed form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.80	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	3.60	cum
4	Providing and placing in position reinforcement for R.C.C. work including .. drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	144.00	kg
5	Providing and fixing formwork including entering Foundations, footings, base of columns and plinth beam in any shape and size.	42.00	sqm
6	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	2.40	cum
1	PWD ROAD SOR (01.01.2015) Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	69.66	cum
2	surface dressing	387.00	cum
3	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads		
	P.C.C. M-10	23.22	cum
	P.C.C. M-25	77.40	cum
3	Carriage by mechanical transport for 5 km lead:		
	Earth	76.26	cum
			
	ASSISTANT ENGINEER		
	NAGAR PALIK NIGAM, BHILAI	SUB ENGINEER	
		NAGAR PALIK NIGAM, BHILAI	