

NAGAR PALIK NIGAM BHILAI

NIT

वार्ड क्र.-21 कैलाश नगर बंगाली मोहल्ला के विभिन्न स्थानों में नाली संधारण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)

S.N	PARTICULAR	Q	U
1	Excavation for all types and sizes of foundations, trenches and drains 0.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	27.00	cum
2	Providing and laying nominal mix cement concrete with crushed form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	4.50	cum
3	Providing and fixing formwork including centering,..... Foundations, footings, base of columns and plinth beam in any shape and size.	90.00	sqm
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	10.50	cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 415	420.00	kg
6	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	4.00	cum
7	Carriage by mechanical transport for 5 km lead: Earth	25.65	cum
ASSTT.ENGINEER Nagar Palik Nigam, Bhilai		SUB ENGINEER Nagar Palik Nigam, Bhilai	