

4



P

NAGAR PALIK NIGAM BHILAI

NIT

पार्षद निधि अंतर्गत वार्ड क्र.-29 वृन्दानगर में बोर खनन कार्य।

AS PER P.W.D BUILDING S.O.R (01.01.2015)

S.No.	PARTICULARS	QTY	UNIT
1	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground level. All types of soil 150 mm dia.	60.00	M
2	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground level. Rocky strata including Boulders. 150 mm dia.	120.00	M
3	Supplying, assembling, lowering and fixing in vertical position in bore well, ISI marked G.I. casing pipe (Plain) medium .IVth revision (Up-to-date amendments), of reputed & approved make, including required hire & labour charges, fittings & accessories, all complete, for all depths, as per direction of Engineer- in-charge. 150 mm nominal dia	62.60	M
4	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for bore well of: 150 mm dia	2.00	Each
			
ASSTT.ENGINEER Nagar Palik Nigam, Bhilai		 SUB ENGINEER Nagar Palik Nigam, Bhilai	