



(11)

**NAGAR PALIK NIGAM BHILAI****NIT**

महानगर निधि अंतर्गत वार्ड क्र.-21 कैलाश नगर कुरुद के भगत सिंह मार्ग के विभिन्न मार्गों में नाली सहित सीमेंटीकरण रोड निर्माण कार्य।

(As per P.W.D BUILDING/ROAD S.O.R. W.E.F. 01.01.2015)

S.N.	PARTICULAR	Q	U
1	Excavation for all types and sizes of foundations, trenches and drains 0.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	40.50	cum
2	Providing and laying nominal mix cement concrete with crushed ..... form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	4.50	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	15.75	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	945.00	Kg
5	Providing and fixing formwork including entering ..... Foundations, footings, base of columns and plinth beam in any shape and size.	60.00	sqm
6	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	6.00	cum
7	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	162.00	cum
8	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	54.00	cum
9	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. ( For Village roads		
	P.C.C. M-10	54.00	cum
	P.C.C. M-25	84.00	cum
10	Carriage by mechanical transport upto 5 km lead:		
	Earth	192.38	cum
			
	<b>ASSTT. ENGINEER</b>		
	Nagar Palik Nigam, Bhilai		
			
	<b>SUB ENGINEER</b>		
	Nagar Palik Nigam, Bhilai		