


MUNICIPAL CORPORATION OF BHILAI


NIT

विषय – वार्ड 04 नेहरु नगर ब्रीज के पास वेडिंग जोन में पेवर ब्लॉक लगाने का कार्य।

S.N.	PARTICULERS OF ITEMS	No	L	B	H/D	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.						
	In all types of soil						
		1	38.00	12.60	0.20	95.76	
						95.76	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).						
		2	51.20	0.20	0.20	4.10	
						4.10	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).						
		1	38.00	12.60	0.10	47.88	
						47.88	Cum
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.						
		1	38.00	12.60	0.10	47.88	
						47.88	Cum
5	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks						
		1	38.00	12.60		478.80	
						478.80	sqm


S.N.	PARTICULARS OF ITEMS	No	L	B	H/D	Quantity	UOM
6	Carriage by mechanical transport upto 5 km lead: Earth						
		1	38.00	12.60	0.20	95.76	
						95.76	Cum


 Asst. Engineer
 Municipal Corporation
 Bhilai


 Sub Engineer
 Municipal Corporation
 Bhilai

MUNICIPAL CORPORATION OF BHILAI
NIT
CHAMBER COVER


S.N.	PARTICULERS OF ITEMS	No	L	B	H/D	Quantity	UOM
1	Providing & placing in position reinforcement for RCC work including straightening cutting bending binding as per drawing including cost of binding wire all complete thermo mechanically treated bars @ 54.50/kg					50	kg
	Providing & laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 1:11/2:3 aggregate 20 mm nominal size + extra precast PCC/RCC work of any mix including form work hoisting and fixing in cement mortar 1:2(1 cement:2 coarse sand & finishing with cement plaster in cement mortar					0.96	cum



Asst. Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai

MUNICIPAL CORPORATION OF BHILAI
NIT
LANDSCAPE & HORTICULTURE WORK

S.N.	PARTICULERS OF ITEMS	No	L	B	H/D	Quantity	UOM
1	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).						
		1				10.00	
					G. Total	10.00	Cum
2	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).						
		1				10.00	
					G. Total	10.00	Cum
3	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand: Hedges like Alife, Dorenta, Tikoma etc						
		50				50	
					G. Total	50	Each
4	Furn like Arica, China etc (3 year old)						
		25				25	
					G. Total	25	Each
5	Hibiscus (Flower)/ Rose						
		25				25	
					G. Total	25	Each
	NON SOR ITEM						
6	Gray round cemented plants pot			15			Each


Asst. Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai