

18


NAGAR PALIK NIGAM BHILAI

NIT

विद्युत निधि अंतर्गत वार्ड क0 29 वृंदानगर प्रवास आन्ध्र स्कूल के पास सार्वजनिक सामुदायिक भवन निर्माण कार्य।

AS PER PWD BUILDING S.O.R 01.01.2015 & ELEC. 01.06.2020

SN	PARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or forupto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.In all types of soil		
		24.78	cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		8.80	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.1:1½:3 (1 cement : ½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		21.13	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Cold twisted bar / Hot rolled deformed steel		
		1901.30	kg
5	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
5.a	Foundations, footings, base of columns and plinth beam in any shape and size.		
		30.80	sqm
5.b	Columns, Pillars, Piers and likes- rectangular or square in shape		
		71.00	sqm
5.c	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)		
		130.58	sqm
5.d	Beams, lintels, cantilevers & walls		
		39.00	sqm
6	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)		
		4.92	cum
7	super structure Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)		
		16.22	cum
8	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.		
		24.00	cum
9	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including formwork		
		0.32	sqm
10	Providing and fixing steel door with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of .. all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer..		
		127.20	kg

11	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat of red oxide zinc chromate primer.		
		81.08	sqm
12	6 mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)		
		85.20	sqm
13	12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)		
		114.00	sqm
14	15mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)		
		60.00	sqm
15	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.		
		166.28	sqm
17	Distempering with washable distemper manufactured with the cow dung processing to give an even shade. On new work (one or more coats)		
		114.00	sqm
18	Painting exterior surface with SMOOTH exterior emulsion paint of manufacturerd with cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (One or more coats applied @ 1.43 ltr/ 10 sqm)		
		21.36	sqm
19	Painting on new work (two or more coats) to give an even shade with.Premium synthetic enamel paint (2nd top most approved branded quality) to give an even shade .		
	ADD EXTRA 3 % FOR ELECTRIFICATION		
	ADD EXTRA 3 % FOR SANITORY		
			
ASSTT.ENGINEER		SUB ENGINEER	
Nagar Palik Nigam, Bhilai		Nagar Palik Nigam, Bhilai	
EXECUTIVE ENGINEER			
Nagar Palik Nigam, Bhilai			