


MUNICIPAL CORPORATION OF BHILAI
NIT

कार्य का नाम-वार्ड 55 (पुराना वार्ड 49) सेक्टर 02 सड़क 02, ब्लॉक क्रं. 10 के समीप मंच
निर्माण एवं शेड निर्माण का कार्य।


(As Per PWD Building SOR 01.01.2015,)

S.N.	PARTICULARS OF ITEMS	QTY	UOM
1	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars	664.7	Kg
2	Steel work in tubular (round, square or rectangular hollow tubes etc.)structure in built-up sections, trusses and frame work including cutting,hoisting, fixing in position upto a height of 5m above plinth level,consisting of columns trusses, roof and bottom purlins, base plate, holdingdown bolts, wind ties bracing (if required), bolts, nuts and washers forfastening etc. complete with applying a priming coat of red oxide zincchromate primer.9.3.1 Electric resistance or induction butt welded tubes Grade-250 (Page79,Item-9.3.1)	1494.00	Kg
3	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	14.4	Sqm
4	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	17.4	Sqm
5	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	23.06	Cum
6	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	17.5	Cum
7	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.SS Grade 204	53	Kg
8	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.Size upto 200x300mm	14.4	Sqm
9	Supply and fixing of precoated galvanized iron profile sheets (size, shapeand pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/-5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in240mpa steel grade, 5-7 microns epoxy primer on both side of the sheetand polyester top coat 15-18 microns. Sheet should have protective guardfilm of 25 microns minimum to avoid scratches while transportation andshould be supplied in single length upto 12 metre or as desired byEngineer-in-charge. The sheet shall be fixed using self drilling /selftapping screws of size (5.5x 55mm) with EPDM seal or with polymercoated J orLhooks,boltsandnuts8mmdiameter with bitumen and G.I.limpet washers or with G.I. limpet washers filled with whiteleadcompleteuptoanypitchinhorizontal/ vertical or curvedsurfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shapewherever required.	25.00	Sqm

10	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	12	Sqm
11	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.85	Cum
12	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:Cement Mortar 1:6 (1 cement : 6 coarse sand)	3.05	Cum
13	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size)(Page-22,Item-3.1.2)	2.03	Cum
14	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand ; 3 graded stone aggregate 20mm nominal size).	6.647	Cum


 कार्यपालन अभियन्ता
 नगर पालिक निगम, भिलाई


 सहायक अभियन्ता
 नगर पालिक निगम, भिलाई


 कार्यपालन अभियन्ता
 नगर पालिक निगम, भिलाई