

**MUNICIPAL CORPORATION BHILAI (C.G.)**  
**NIT**


कार्य का नाम :- वार्ड 03 कोसानगर स्थित शासकीय प्रा.शाला का संधारण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.06.2020)

S.No.	Description and details of work	Qty.	Unit
1	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.	120.00	Sqm
2	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:In Cement Mortar 1:6 (1 cement : 6 fine sand)	240.00	Sqm
3	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. 12.9.1 Size 300x300mm	456.00	Sqm
4	Providing and applying 2mm thick ready mix exterior grade approved make putty (manufactured with cow dung processing) on walls to make the surface smooth and even.	1128.75	Sqm
5	Wall painting with premium emulsion (plastic)manufactured with cow dungprocessing emulsion paint of required shade to give e an even shade On new work (two or more coats)	760.86	Sqm
6	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with cow dung to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/10 sqm)	708.86	Sqm
7	Painting on old work (one or more coats) to give an even shade with: Satin synthetic enamel paint	300.00	Sqm
8	Add Electrification Work 4%	23057.00	Rs

**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Sub. Engineer**  
**Municipal Corporatio**  
**Bhilai (C.G)**