

MUNICIPAL CORPORATION BHILAI (C.G.)
NIT

कार्य का नाम :- वार्ड 04 कृष्णा नगर स्थित शासकीय प्रा.शाला का संधारण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.06.2020)

S.No.	Description and details of work	Qty.	Unit
1	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.	198.00	Sqm
2	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. 12.7.1 Size upto 200x300mm	18.00	Sqm
3	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. 12.9.1 Size 300x300mm	220.00	Sqm
4	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:		
5	In Cement Mortar 1:5 (1 cement : 5 fine sand)	360.00	Sqm
6	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	420.00	Kg
7	Providing and applying 2mm thick ready mix exterior grade approved make putty (manufactured with cow dung processing) on walls to make the surface smooth and even.	935.64	Sqm
8	Wall painting with premium emulsion (plastic)manufactured with cow dungprocessing emulsion paint of required shade to give e an even shade On new work (two or more coats)	1000.00	Sqm
9	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with cow dung to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/10 sqm)	1772.15	Sqm
10	Painting on old work (one or more coats) to give an even shade with: Satin synthetic enamel paint	300.00	Sqm
11	Add Electrification Work 4%	23057.00	Rs

Executive Engineer
Municipal Corporation
Bhilai (C.G)

Asstt. Engineer
Municipal Corporation
Bhilai (C.G)

Sub. Engineer
Municipal Corporatio
Bhilai (C.G)