

# MUNICIPAL CORPORATION BHILAI (C.G.)

## NIT

कार्य का नाम :- वार्ड-07 फरीद नगर में स्थित शासकीय प्रा.शाला का संधारण कार्य।


(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.06.2020)


S.No.	Description and details of work	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	5.00	Cum
2	Dismantling bricks laid flat or on edge (each layer), or cement concrete tiles in flooring or over roofs in cement/lime mortar including stacking of serviceable material and disposal of unserviceable material within 50 metre	30.00	Sqm
3	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within	42.00	Sqm
4	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete	100.00	Kg
5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	2.08	Sqm
6	25mm thick Local RAJIM/ Red Flag stone slab in riser of steps, skirting, dado and pillars laid on 12mm (Average) thick cement mortar 1:4 (1 cement : 4 coarse sand) and joint with grey cement slurry mixed with pigments to match the shade of the slab i/c grinding, rubbing and polishing.	9.00	Sqm
7	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.27	Cum
8	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.	72.00	Sqm
9	15mm thick Granite work (machine cut, table rubbed & mirror polished) for wall lining (veneer work) in cement mortar 1:3 (1 cement : 3 coarse sand) including pointing with cement mortar 1:2 (1 white cement: 2 marble dust) mixed with matching pigment. (Area of slab should be over 0.5 sqm). Granite stone black	4.24	Sqm
10	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6(1 cement : 6 fine sand)	81.36	Sqm
11	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size 200x300mm	45.00	Sqm

S.No.	Description and details of work	Qty.	Unit
12	Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug 40mm C.P brass waste and 40mm C.P. brass trap with necessary C.P. brass unions complete including painting of brackets, cutting and making good the wall wherever required : Size 600x450x200mm	2.00	Each
13	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
14	20 mm dia. nominal bore	40.00	Mtr
15	25 mm dia. nominal bore	50.00	Mtr
16	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	4.00	Each
17	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:		
18	Soap dish plate	3.00	Each
19	Towel rail (600mm long x 20mm dia)	3.00	Each
20	Providing and fixing double glazed hermetically sealed glazing in aluminium windows, ventilators and partition etc. with 6 mm thick clear float glass both side having 12 mm air gap including providing EPDM gasket, perforated aluminium spacers, desiccants, sealant (Both primary and secondary sealant) etc. complete.	6.30	Sqm
21	Providing and applying plaster of paris putty over plastered wall surface including scaffolding complete Upto 2 mm thickness to make surface even and smooth in line and level.	2000.00	Sqm
22	Wall painting with premium emulsion (plastic)manufactured with cow dungprocessing emulsion paint of required shade to give e an even shade On Old work (two or more coats)	1634.15	Sqm
23	Painting on old work (one or more coats) to give an even shade with: Satin synthetic enamel paint	32.76	Sqm
24	Providing and fixing "NETLON insect screens" with 25mm wide Hook and loop tape all around to wooden/ aluminium/ steel windows, ventilators and the like complete	12.00	Sqm
25	Providing and replacing broken floor tile with ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including removing the broken tile and mortar, pointing the joints with white cement mixed with matching pigment etc., complete.	60.00	Sqm
26	Providing and fixing aluminium work for doors, windows, ventilators and made out of extruded aluminium standard sections (main.....indows, ventilators and partitions made out of extruded aluminium standard sections (main section with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285 mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gasket beveled edge beading, screws duly fixed in wall/	50.00	Kg

S.No.	Description and details of work	Qty.	Unit
27	For shutter of doors, windows & ventilators including providing and making provision for fixing of fitting wherever required including the cost of PVC/ neoprene gasket required (Fittings shall be paid for separately).	50.00	kg
28	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	200.00	Kg
29	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with cow dung to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/10 sqm)	753.16	Sqm
30	Lettering with black Japan paint, per cm height.	1500.00	per Letter
31	ADD EXTRA 5 % FOR ELECTRIFICATION	27078.00	Rs
32	ADD EXTRA 5 % FOR SANITORY	27078.00	Rs

Executive Engineer  
Municipal Corporation  
Bhilai (C.G)

  
Asstt. Engineer  
Municipal Corporation  
Bhilai (C.G)

  
Sub. Engineer  
Municipal Corporatio  
Bhilai (C.G)