

# MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 40 शंकर नगर, छावनी स्थित क्रिकेट मैदान में क्रिकेट चेम्बर (स्टील जाली वाला) लगाने का कार्य।

(As Per PWD Building SOR 01.01.2015)

| S.N. | PARTICULERS OF ITEMS   | Quantity | UOM  |
|------|--|----------|------|
| 1    | Surface dressing of the ground including removing vegetation and making up undulations and inequalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).  | 82.57    | Sqm  |
| 2    | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.            | 33.60    | Cum  |
| 3    | Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).   | 160.96   | Cum  |
| 4    | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.  | 16.51    | Cum  |
| 5    | Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:<br>40 mm dia. nominal bore   | 18.00    | Mtr. |
| 6    | Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete.<br>Aperture 50x50mm | 247.00   | Sqm  |
| 7    | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.<br>1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).                                       | 4.24     | Cum  |



**Executive Engineer**  
Municipal Corporation  
Bhilai

**Assistant Engineer**  
Municipal Corporation  
Bhilai



**Sub Engineer**  
Municipal Corporation  
Bhilai