


# MUNICIPAL CORPORATION OF BHILAI

## NIT


कार्य का नाम :-जोन 03 क्षेत्रांतर्गत वार्ड क्रमांक 36 पिंक टायलेट के पास वेडिंग जोन निर्माण कार्य।

As Per PWD Building SOR 01.01.2015

S.N	PARTICULERS OF ITEMS	Quantity	UOM	Rate
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.In all types of soil	102.00	Cum	185.00
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	51.00	Cum	2970.00
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	4.88	Cum	4073.00
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	51.00	Cum	371.00
5	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	510.00	sqm	632.00

  
कार्यपालन अभियन्ता  
नगर पालिक निगम, भिलाई

  
सहायक अभियन्ता  
नगर पालिक निगम, भिलाई

  
उप अभियन्ता  
नगर पालिक निगम, भिलाई