

3

MUNICIPAL CORPORATION OF BHILAI


NIT


कार्य का नाम – निगम क्षेत्र में चौक चौराहों में वर्टिकल गार्डन लगाने का कार्य।

S.N.	PARTICULERS OF ITEMS	Qty	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.		
	In all types of soils.	250	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	100	cum
3	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:		
	Cement Mortar 1:6 (1 cement : 6 coarse sand)	72	cum
4	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.		
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	3568	kg
5	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete.		
	Aperture 50x50mm	720	Sqm
6	Providing and making 12mm thick cement plaster of mix:		
	In Cement Mortar 1:6 (1 cement : 6 fine sand)	120	Sqm
7	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).	800	cum

(4)


8	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).	100	cum
9	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand: Hedges like Alife, Dorenta, Tikoma etc	8000	each
10	Hibiscus (Flower)/ Rose	1500	each
11	Carpet grass (well developed)	100	Sqm
12	Providing and Fixing Polypropylene mat finish frame size Length 6" height 18" fixing 3 nos of pot material of pot polypropylene, pot size Length 6" Hight 4.4"	2000	each
13	Devlopment of Garden etc preparation of soil base, plantation,sculpturing work, Electric Fitting, stone work providing and spreading different fertilizers, black soil and sand e/c Labour cost of all item e/c complete with details below (Labour cost extra) Cycus Vericted Champa Fycus	20 20 20	each each each
14	Labour coast for supervision & consultig charges.		


सहायक अभियन्ता
नगर पालिक निगम, भिलाई


उप अभियन्ता
नगर पालिक निगम, भिलाई

TERMS AND CONDITIONS FOR TENDER FOR WORK OF VERTICAL GARDEN

1. EMD, PWD Live Registration copy, 3 month GST certificate copy , Bank Solvency certificate, copy of last 3 years income tax return certificate and Affidavit on Non Judicial Stamp worth Rs.100/- should be essentially submitted by the Tendrer along with Other necessary documents by Registered / Speed Post.
2. 3 nos. of minimum work order copy of 20 lakhs from any govt. /semi govt. for the landscape development/garden work should submit along with other documents.
3. The detail 3 D conceptual plan for Vertical garden /landscape development should be submitted along with necessary documents.
4. As this is specialized work therefore tendrer should have the minimum BSc Horticulture/Agriculture degree from recognize university and should submit the same along with necessary documents and also submit the documents for qualified civil engineer (diploma/ degree) with him to execute the work.
5. 5 nos. A4 size of photographs of minimum two completed work of garden /landscape should submit with necessary documents.


Sub Engineer
Municipal Corporation
Bhilai