



(10)

## NAGAR PALIK NIGAM BHILAI

NIT

जोन क्र.-02 वैशालीनगर क्षेत्रांतर्गत सी.सी. रोड संधारण कार्य।

(As per P.W.D BUILDING/ROAD S.O.R. W.E.F. 01.01.2015)

S.N.	PARTICULAR	QTY	UNIT
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	49.50	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	16.50	cum
3	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads)		
	P.C.C. M-10	16.50	cum
	P.C.C. M-25	20.63	cum
4	Carriage by mechanical transport upto 5 km lead:		
	Earth	39.60	cum
			
	<b>ASSTT.ENGINEER</b>		
	<b>Nagar Palik Nigam, Bhilai</b>		
			
	<b>SUB ENGINEER</b>		
	<b>Nagar Palik Nigam, Bhilai</b>		