

MUNICIPAL CORPORATION OF BHILAI

NIT

जोन क्र. 04 खुर्सीपार क्षेत्रांतर्गत वार्डों में स्ट्रीट लाईट संधारण एवं केबल वायर प्रदाय कार्य।

(Electrical SOR 01-06-2020 & NON SOR ITEM)


S.N.	PARTICULERS OF ITEMS	Quantity	UOM	
1	Supplying and laying following sizes additional one number, FRLS PVC insulated /XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground as in the same trench in one tier horizontal formation at a depth not less than 40 cm and upto 90 cm including excavation, sand cushioning, protective covering and refilling the trench etc as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1). 4 x 25 sq. mm.	400.00	Metre	
2	Supplying and laying following sizes one number FRLS PVC insulated /XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade in existing RCC/ HUME/ STONEWARE/ METAL/ HDPE pipe as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1). 4 x 25 sq. mm.	450.00	Metre	
NON SOR ITEM				Rate
1	PVC Wire 10mm	40	Role	
2	PVC Wire 6mm	60	Role	
3	PVC Wire 4mm	50	Role	



Executive Engineer
Municipal Corporation
Bhilai



Assistant Engineer
Municipal Corporation
Bhilai



Sub Engineer
Municipal Corporation
Bhilai