MUNICIPAL CORPORATION OF BHILAI

<u>NIT</u> नर्य का नाम :— वार्ड कं. 57 सेक्टर 4 सड़क 5 से लेकर 10 तक एवं 7,8 में नाली निर्माण कार्य।

SN.	Details of Item		
	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including drassing and the sizes.	Qty.	Unit
1	for any other purpose Including dressing and leveling of pits. In all types of soil.		
	@ Rs.185.00/m ³	240.03	Cum
	Providing and laying nominal mix company		
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form works 1.4.004		
	excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded		
	stone aggregate 40mm nominal size)	34.29	Cum
	@ Rs.2659.00/m ³		
3	Providing and fixing formwork I/c centering, shuttering, strutting, staging,		
	propping bracing etc. complete and including its removal at all levels, for:		
	a)Foundations, footings; base of columns and plinth beam in any shape	838.20	Sqm
	and size		
	@ Rs. 139.00/m ²		
4	Providing and laying nominal mix reinforcement cement concrete with		
	crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	83.82	Sqm
	@ Rs. 4163.00/m ³		
5	Providing and laying nominal mix plain cement concrete with crushed stone		
	aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:11/2:3 (1 cement: 11/2 coarse sand: 3 graded stone	34.29	Cum
	aggregate 20mm nominal size).		
	ce c		-
6	Providing and filling in plinth with sand/ Crusher dust and hard moorum		
	under floor in layers not exceeding 20cm in depth consolidating each	13.716	Cum
	deposited layer by ramming and watering, including dressing etc. complete.		
	1 (SC/Tourleding rook) in transher plinth		
7	Filling from available excavated stuff (Excluding rock) in trenches, plinth,		
	sides of foundation etc. in layers not exceeding 20cm in depth		
	consolidating each deposited layer by ramming and watering with a lead	32.004	Cum
	upto 50 M. and lift upto 1.5 M.		
	- Work including		
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings		
	including cost of binding wire all complete. Thermo-Mechanically treated	4191.000	Kg
		131.000	, ''s
	bars. @ Rs. 54.50/kg.		
	(W. U.S. 04.00/kg.		
9			
	Carriage by mechanical transport for 5 km lead.	192.020	Cum
	@ Rs.111.00/m ³		

√ Asstt. Engineer Municipal Corporation Bhilai(C.G.)

Engineer Municipal Corporation Bhilai(C.G.)