



# MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- पेवर ब्लॉक लगाने का कार्य।

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.(In all types of soils.)	27.60	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	13.80	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 1 coarse sand : 4 graded stone aggregate nominal size).	13.80	Cum
3	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	138.00	SQM
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	2.926	Cum
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	24.84	Cum

  
Asstt. Engineer  
Municipal Corporation  
Bhilai(C.G.)

  
Sub Engineer  
Municipal Corporation  
Bhilai(C.G.)

# MUNICIPAL CORPORATION OF BHILAI

## NIT

कार्य का नाम :- आर.सी.सी नाली निर्माण।

SN.	Details of Item	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil. @ Rs.185.00/m <sup>3</sup>	96.39	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) @ Rs.2659.00/m <sup>3</sup>	13.77	Cum
3	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size @ Rs. 139.00/m <sup>2</sup>	336.6	Sqm
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3 @ Rs. 4163.00/m <sup>3</sup>	33.66	Sqm
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	13.77	Cum
6	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	5.508	Cum
7	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	12.852	Cum

8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars. @ Rs. 54.50/kg.	1683	Kg
9	Carriage by mechanical transport for 5 km lead. @ Rs.111.00/m <sup>3</sup>	77.112	Cum

*for*  
*rbh*  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai(C.G.)**

*[Signature]*  
**Sub. Engineer**  
**Municipal Corporation**  
**Bhilai(C.G.)**


# NAGAR PALIK NIGAM BHILAI


NIT

सीसी रोड निर्माण कार्य।

(As per P.W.D Road S.O.R. 01.01.2015)

S.NO	PARTICULAR	Q	U
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads)		
	P.C.C. M-10	12.80	cum
2	P.C.C. M-30	95.40	cum

  
Asstt. Engineer  
Municipal Corporation  
Bhilai(C.G.)

  
Sub Engineer  
Municipal Corporation  
Bhilai(C.G.)