



(2)

## NAGAR PALIK NIGAM BHILAI

NIT

अधोसंरचना मद अंतर्गत वार्ड क्र.-28 प्रेमनगर आन्धा स्कूल के पीछे एवं मस्जिद के पास सीमेंटीकरण कार्य।

(As per P.W.D BUILDING/ROAD S.O.R. W.E.F. 01.01.2015)

S.N.	PARTICULAR	QTY	UNIT
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	295.92	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	98.64	cum
3	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. ( For Village roads	98.64	cum
	P.C.C. M-10	147.96	cum
	P.C.C. M-30		
4	Carriage by mechanical transport upto 5 km lead:		
	Earth	149.14	cum
			
	ASSTT.ENGINEER		
	Nagar Palik Nigam, Bhilai	SUB-ENGINEER	
		Nagar Palik Nigam, Bhilai	