(3)

NAGAR NIGAM BHILAI

NIT

अधोसरचना मद अंतर्गत वार्ड क्र.—24 हाउसिंग बोर्ड के विभिन्न स्थानों में पेवर ब्लॉक लगाने का कार्य।

AS PER BUILDING SOR 01.01.2015

S.N	PARTICULAR AS I EN BOILDING SON OROMESTS	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other		
	purposeupto 50m (at least 5m away from the excavated area), including dressing and		
	leveling of pits.		
	In all types of soil	267.60	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in		
	layers not exceeding 20cm in depth consolidating each deposited layer by ramming and		
	watering, including dressing etc. complete.		
		133.80	cum
3	Providing & laying 60mm thick precast interlocking concrete blocks of approved over 40		
	mm thick including leveling with surface vibrator, temping and sweeping etc. complete		
	of minimum compressive strength of 250 kg/sq.cm		
	Pigment Coloured (rubber mould) precast interlock concrete blocks		
		1338.00	sqm
4	Providing and laying nominal mix plain cement using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		13.47	cum
Print			
ASSTT.ENGINEER SUB ENGINEER			
Nagar Palik Nigam, Bhilai Nagar Palik Nigam, Bhilai			