


MUNICIPAL CORPORATION BHILAI


NIT


कार्य का नाम :-वार्ड क्रमांक 52 सेक्टर 04 सड़क 01 में अर.सी.सी. नाली निर्माण कार्य।

As Per PWD Building SOR 01.01.2015

SN.	Details of Item	Qty.	UNIT
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.In cement mortar.	20.90	Cum
2	Demolishing cement concrete including disposal of material within 50 metre lead.1:3:6 or richer mix	20.90	Cum
3	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	131.67	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	37.62	Cum
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	96.14	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete.Thermo-Mechanically treated bars.	5768.40	Kg
7	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	836.00	Sqm
8	Carriage by mechanical transport for 5 km lead. Earth	138.78	Cum


कार्यपालन अभियन्ता
नगर पालिक निगम, मिलाई


सहायक अभियन्ता
नगर पालिक निगम, मिलाई


उप अभियन्ता
नगर पालिक निगम, मिलाई