

MUNICIPAL CORPORATION BHILAI

NIT

कार्य का नाम :-वार्ड 55 में विवेकानंद स्कूल के सामने सड़क 09 से 14 तक नाली पुलिया सहित निर्माण कार्य।

As Per PWD Building SOR 01.01.2015

| SN. | Details of Item | Qty. | UNIT |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------|
| 1 | Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar. | 18.10 | Cum |
| 2 | Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix | 18.10 | Cum |
| 3 | Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil. | 114.03 | Cum |
| 4 | Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size). | 32.58 | Cum |
| 5 | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 83.26 | Cum |
| 6 | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement. | 28.96 | Cum |
| 7 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars. | 4995.60 | Kg |
| 8 | Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size | 724.00 | Sqm |
| 9 | Carriage by mechanical transport for 5 km lead. Earth | 120.18 | Cum |

कार्यपालन अभियन्ता
नगर पालिक निगम, मिलालई

सहायक अभियन्ता
नगर पालिक निगम, मिलालई

उप अभियन्ता
नगर पालिक निगम, मिलालई