


# MUNICIPAL CORPORATION BHILAI (C.G.)


## NIT


कार्य का नाम :- वार्ड-1 खम्हरिया भाठा में शिव मंदिर से सुमरित मोहल्ला मंच तक आर.सी.सी. नाली एवं सी.सी. रोड निर्माण कार्य।

Pwd Building /Road Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	97.20	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	16.20	Cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	34.20	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete.Thermo-Mechanically treated bars.	3078.00	KG
5	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	288.00	Sqm
6	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	14.40	Cum
7	Carriage by mechanical transport for 5 km lead.	97.20	Cum
9	Providing and laying Cement Concrete for plain concrete/reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C.M.-10	21.00	Cum
9	Providing and laying Cement Concrete for plain concrete/reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C.M.-30	119.00	Cum

  
**Executive Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Asstt. Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Sub. Engineer**  
Municipal Corporatio  
Bhilai (C.G)