

# MUNICIPAL CORPORATION BHILAI (C.G.)

## NIT


कार्य का नाम :- वार्ड-05 कोसानगर मॉडल टाउन स्ट्रीट नंबर 11,12 एवं अन्य क्षेत्रों में सीमेंटीकरण कार्य।

Pwd Road Sor 01.01.2015


S.No.	Description and details of work	Qty.	Unit
1	Excavation in Soil (by Manual Means.) Excavation for roadway in soil using including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	302.64	Cum
2	Granular Sub-base as per Table:- 400-1 Construction of granular sub-base by providing graded Material, , carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density, complete as per clause 401 Disintegrated rock i.e moorum having CBR value not less than 20 and P.I. and L.L. not more than 6 and 20 respectively. (For Village roads only)	100.88	Cum
3	Providing and laying Cement Concrete for plain concrete/reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C.M.-10	98.94	Cum
4	Providing and laying Cement Concrete for plain concrete/reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C.M.-30	145.50	Cum



**Executive Engineer**  
Municipal Corporation  
Bhilai (C.G)



**Asstt. Engineer**  
Municipal Corporation  
Bhilai (C.G)



**Sub. Engineer**  
Municipal Corporation  
Bhilai (C.G)