

S.N.

Provi'
sect'
sr

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 46, दुर्गा मंदिर के ज्योति नगर में सीमेंटीकरण एवं मिनीमाता नगर में नाली संघारण कार्य।

(As Per PWD Building & Road SOR 01.01.2015)

| SN | PARTICULERS OF ITEMS | QTY. | UNIT |
|----|--|--------|------|
| 1 | Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 Meter lead. In cement mortar. | 24.00 | Cum |
| 2 | Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil. | 48.00 | Cum |
| 3 | Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) | 16.00 | Cum |
| 4 | Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size | 360.00 | Sqm |
| 5 | Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3 | 33.00 | Cum |
| 6 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete.Thermo-Mechanically treated bars. | 990.00 | Kg |
| 7 | Carriage by mechanical transport for 5 km lead. Earth | 57.60 | Cum |
| 8 | <u>Road SOR 01.01.2015</u> Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) | | |
| | P.C.C. M-10 | 9.00 | Cum |
| | P.C.C. M-25 | 39.38 | Cum |



Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai



Sub Engineer
Municipal Corporation
Bhilai