

MUNICIPAL CORPORATION OF BHILAI
NIT


वार्ड क्र. 48 जोन 03 खुर्सीपार में पाईप लाईन विस्तारीकरण कार्य ।

(As Per PWD Building SOR 01.01.2015)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	40.00	Cum
2	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	50 mm dia. nominal bore	400.00	Metre
	40 mm dia. nominal bore	150.00	Metre
	25 mm dia. nominal bore	150.00	Metre
	15 mm dia. nominal bore	100.00	Metre
3	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	100.00	Cum
4	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	50 mm dia. nominal bore	5	each
	40 mm dia. nominal bore	5	each
5	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	70	each


Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai