

# MUNICIPAL CORPORATION OF BHILAI

## NIT


कार्य का नाम— जोन कं. 05 अंतर्गत विभिन्न वार्डों में सीमेंटीकृत मार्ग एवं जर्जर नालियों संधारण कार्य।

1	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	579.00	sqm.
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.(In all types of soils.)	418.80	Cum
3	Carriage by mechanical transport for 5 km lead. @ Rs.111.00/m <sup>3</sup>	447.75	Cum
4	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads) P.C.C. M-25 (	57.90	Cum
5	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads) P.C.C. M-30	115.80	Cum
6	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)	115.80	Cum
7	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead In cement mortar.	78.00	Cum
8	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	52.00	Cum
9	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	1170.00	Cum

10	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.	107.25	SQM
11	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:	3217.500	Cum



**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai(C.G.)**



**Sub Engineer**  
**Municipal Corporation**  
**Bhilai(C.G.)**