


# MUNICIPAL CORPORATION BHILAI (C.G.)


NIT


कार्य का नाम :- जोग-01 अंतर्गत विभिन्न स्थानों में पुलिया संधारण कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	46.80	Cum
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	156.00	Cum
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	31.20	Cum
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	134.55	Cum
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3	27.30	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	1638.00	KG
7	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	40.95	Cum
8	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	943.80	Sqm
9	Carriage by mechanical transport upto 5 km lead:	202.80	Cum

  
**Executive Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Asstt. Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Sub. Engineer**  
Municipal Corporatio  
Bhilai (C.G)