NAGAR PALIK NIGAM BHILAI



वार्ड क्र.—26 रामनगर शिवा लान्ड्री (दशरथ निर्मलकर) निवास से होते हुए दौलत देवांगन निवास तक सीमेंटीकरण कार्य।

SN	PARTICULAR AS PER ROAD/BUILDING SOR (01.01.2015)		
	AKITCULAR	QTY	UNIT
	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.		
		292.50	cum
	Providing and filling in plinth with sand/ Crusher dust and hard moorumunder floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.		
	· ·	97.50	cum
	Providing and laying cement concrete for plain concrete/reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads		
	P.C.C. M-10	97.50	cum
	P.C.C. M-30	146.25	cum
4	Carriage by mechanical transport upto 5 km lead:		
	Earth	248.63	cum
	(3)		,
	ASSISTANT ENGINEER SUB ENGINEER	1	
1	NAGAR PALIK NIGAM, BHILAI NAGAR PALIK NIGAM, BHILAI		