


MUNICIPAL CORPORATION OF BHILAI

NIT


वार्ड क्र. 44 लक्ष्मीनारायण नगर, यादव मोहल्ला, राम मंदिर के पीछे एवं सरकारी कुंआ लाईन में सी.सी. रोड संधारण एवं नाली संधारण कार्य।

(As Per PWD Building & Road SOR 01.01.2015)

SN	PARTICULERS OF ITEMS	QTY.	UNIT	
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 Meter lead. In cement mortar.	24.00	Cum	
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	48.00	Cum	
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	16.00	Cum	
4	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	360.00	Sqm	
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	33.00	Cum	
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	990.00	Kg	
7	Carriage by mechanical transport for 5 km lead. Earth	57.60	Cum	
8	<u>Road SOR 01.01.2015</u> Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads)			
		P.C.C. M-10	17.10	Cum
		P.C.C. M-25	150.75	Cum


Executive Engineer
Municipal Corporation
Bhilai


Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai