


# MUNICIPAL CORPORATION BHILAI


## NIT


कार्य का नाम :-वार्ड 56 सेक्टर 02 में सड़क एवेन्यु सी में नाली पुलिया सहित निर्माण कार्य।

As Per PWD Building SOR 01.01.2015

SN.	Details of Item	Qty.	UNIT
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	18.10	Cum
2	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	18.10	Cum
3	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	114.03	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	32.58	Cum
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	83.26	Cum
6	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	28.96	Cum
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	4995.60	Kg
8	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	724.00	Sqm
9	Carriage by mechanical transport for 5 km lead. Earth	120.18	

  
कार्यपालन अभियन्ता  
नगर पालिक निगम, भिलाई

  
सहायक अभियन्ता  
नगर पालिक निगम, भिलाई

  
प्रम. अभियन्ता  
नगर पालिक निगम, भिलाई