

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 39 सुभाष नगर खेल मैदान में स्वागत द्वार निर्माण कार्य।

(As Per PWD Building SOR 01.01.2015)

SN	PARTICULARS OF ITEMS	QTY.	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	20.52	Cum
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil Extra for every additional lift of 1.5 m or part thereof.	9.72	Cum
3	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	7.56	Cum
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	16.42	Cum
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	2.05	Cum
6	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	12.17	Cum
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	973.44	Kg
8	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	11.20	Sqm
9	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Columns, Pillars, Piers and likes- rectangular or square in shape	11.60	Sqm
10	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Columns, Pillars, Piers and likes- rectangular or square in shape. Extra for additional height every 1m or part thereof where height of staging for form work exceeds 4.0 metre with adequate bracing, propping etc at all levels, for suspended floor, roof, landing, beam and balcony. (only plan area is to be measured):	2.88	Sqm
11	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Beams, lintels, cantilevers & walls	9.84	Sqm
12	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	29.32	Sqm
13	Providing and making 6mm thick cement plaster of mix: In Cement Mortar 1:3 (1 cement : 3 fine sand)	4.28	Sqm
14	Providing and applying 2mm thick ready mix exterior grade putty (Manufactured with cow dung processing) on walls to make the surface smooth and even.	33.60	Sqm
15	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with th cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with : On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over)	33.60	Sqm

SN	PARTICULARS OF ITEMS	QTY.	UNIT
16	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	108.00	Kg
17	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	95.10	Kg
18	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	200.40	Kg
19	Providing and fixing aluminium composite panels in approved panel sizes, thickness and shape on aluminium frame work on face of building. (Frame to be paid separately) 4mm thick	3.51	Sqm
20	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	395.00	Kg
21	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	11.64	Sqm


Executive Engineer
 Municipal Corporation
 Bhilai


Assistant Engineer
 Municipal Corporation
 Bhilai


Sub Engineer
 Municipal Corporation
 Bhilai