



NAGAR NIGAM BHILAI

NIT

विधायक निधि अंतर्गत वार्ड क्र.-25 हाउसिंग बोर्ड सार्वजनिक कालीबाड़ी हाउसिंग बोर्ड के प्रांगण में पेवर ब्लॉक लगवाने हेतु।

AS PER BUILDING SOR 01.01.2015

| S.N | PARTICULAR | QTY | UNIT |
|-----|--|---------|------|
| 1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose..upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. | 225.60 | cum |
| | In all types of soil | | |
| 2 | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete. | 580.80 | cum |
| 3 | Providing & laying 60mm thick precast interlocking concrete blocks of approved .. over 40 mm thick .. including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg | 1128.00 | sqm |
| | Pigment Coloured (rubber mould) precast interlock concrete blocks | | |
| 4 | Providing and laying nominal mix plain cement .. using concrete mixer in all works upto plinth level excluding cost of form work. | 4.37 | cum |
| | 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | | |
| 5 | Carriage by mechanical transport upto 5 km lead: | 105.60 | cum |
| | Earth | | |
| |  | | |
| | ASSTT.ENGINEER Nagar Palik Nigam, Bhilai | | |
| |  | | |
| | SUB ENGINEER Nagar Palik Nigam, Bhilai | | |

15/2