

MUNICIPAL CORPORATION OF BHILAI


NIT

कार्य का नाम :- वार्ड क्रं. 69 एवं 70 हुडको के विभिन्न स्थानों पर सीवर लाईन एवं चेम्बर संधारण कार्य।

PWD Building SOR 01.01.2015)

S.No.	Details Of Item	Qty.	Unit
1	Excavation in Soil (by manual Means) Excavation for roadway in soil using including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead up to 1000 meters as per relevant clauses of section 300	127.68	cum
2	Dismantling of old S.W. pipes including breaking of joints and bed concrete stacking of useful materials near the site within 50 m lead but beyond 20m and disposal of unserviceable materials: 150 mm diameter	152	m
3	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design 200 mm diameter S.W. pipe	152.00	m
4	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete : 200 mm diameter	152	m
5	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	127.68	cum
6	Inside size 90x80 cm and 45 cm deep including RCC cover with frame 450x600 mm internal dimensions. Extra for depth for manholes Size 90x80 cm	7.6	nos
7	Inside size 120x90 cm and 90 cm deep including RCC cover with frame 500 mm internal diameter. Extra for depth for manholes Size 120x90 cm	7.6	nos

सहायक अभियन्ता
नगर पालिक निगम, भिलाई


उप अभियन्ता
नगर पालिक निगम भिलाई