

MUNICIPAL CORPORATION BHILAI (C.G.)**NIT****Name of work :-वार्ड कं. 65 सेक्टर 10 उडिया बस्ती में पाईप लाईन संधारण कार्य।****As per Building SOR 01.01.2015**

S.No.	Description and details of work	Qty.	unit
1	Providing and fixing on wall surface G I. pipes medium class complete with G I fittings and clamps, including cutting, making good the walls etc and testing of joints complete: 25 mm dia. nominal bore	15.0	rmt
	20 mm dia. nominal bore	10.0	rmt
	15 mm dia. nominal bore	80.0	rmt
2	Providing ISI Mark 32 mm dia G I (B class) nser pipe and M plunger rod in 3 meter length socketed on one end as per IS 1239 (Part I) 1990 with up to date amendments and socket as per IS 2062/1990 up to date amendment	90.0	rmt
3	Supply, installation, testing and commissioning of 1-3 HP 1 phase submersible motor starter cum control wall/ floor mounted type made out of not less than 1.6 mm thick MS sheet and comprising of following panel mounting switchgears there in including connection inter-connection etc as required a) Phase indicating lamps with fuses and toggle switches 1 set b) 1/2/3 HP 1 phase DOL starter with over load and no volt relay 1 No c) 25 A "C" curve DPMCB 1 No d) Voltmeter 0-250 V 1 set e) Ammeter 0-10 A 1 set	1.0	nos
4	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required	70.0	metre

**Asstt. Engineer
Municipal Corporation
Bhilal(C.G.)**


**Sub Engineer
Municipal Corporation
Bhilal (C.G.)**