

6

# MUNICIPAL CORPORATION OF BHILAI

## NIT


वार्ड क्र. 41, राजीव नगर छावनी में नाली निर्माण एवं सीमेंटीकरण कार्य।

(As Per PWD Building & Road SOR 01.01.2015)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 Meter lead. In cement mortar.	19.20	Cum
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	38.40	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	12.80	Cum
4	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	288.00	Sqm
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	26.40	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	792.00	Kg
7	Carriage by mechanical transport for 5 km lead. Earth	46.08	Cum
8	<u>Road SOR 01.01.2015</u> Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads )		
	P.C.C. M-10	9.50	Cum
	P.C.C. M-25	30.00	Cum

  
Executive Engineer  
Municipal Corporation  
Bhilai

  
Assistant Engineer  
Municipal Corporation  
Bhilai

  
Sub Engineer  
Municipal Corporation  
Bhilai