## MUNICIPAL CORPORATION OF BHILAI

NIT वार्ड क्र. 46 दुर्गा मंदिर के पास सामुदायिक भवन में नई सुविधा तथा विद्युत संधारण कार्य। (पार्षद निधि)

(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.06.2020)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	15 mm thick Table rubbed polished Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (Average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polishing etc. complete (single stone is to be used for risers and treads of steps and width of stone for skirting and dado shall be equal to the height of skirting & dado and length of 1.0 m).	117.60	Sqm
2	Granite stone lakha red/ shahi red Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.  SS Grade 204	140.00	Kg
3	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.  In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	210.000	Kg
4	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	280.000	Sqm
5	Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. On new work (two or more coats)	280.00	Sqm
6	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:  On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	330.00	Sqm
7	Add Extra For Electrification Work	51833.00	LS

**Executive Engineer** Municiapal Corporation Bhilai

Assistant Engineer Municipal Corporation Bhilai

**Municipal Corporation** Bhilai