

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 47 राधाकृष्ण मंदिर, पं. जवाहर लाल नेहरू स्कूल के बाजू में छोटा उद्यान निर्माण कार्य।

(As Per PWD Building/Road SOR 01.01.2015 & Electric SOR 01.06.2020 & NON SOR ITEM)

SN	PARTICULARS OF ITEMS	QTY.	UNIT	
1	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) + Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	13.38	Cum	
2	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	200.70	Sqm	
3	Providing and applying 2mm thick ready mix exterior grade putty (Manufactured with cow dung processing) on walls to make the surface smooth and even.	200.70	Sqm	
4	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with th cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with : On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over)	100.35	Sqm	
5	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).	80.00	Cum	
6	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand: Hedges like Alife, Dorenta, Tikoma etc	100.00	Each	
	Carpet grass (well developed)	100.00	Sqm	
7	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	150.00	Sqm	
8	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1:1 ½ :3 (1 cement : 1 ½ coarse sand :3 graded stone aggregate 20mm nominal size)	1.80	Cum	
9	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars.	90.00	Kg	
8	As per PWD Road SOR 01.01.2015 Cement art Mural work	10.00	Sqm	
13	For Electrification Work (As Per electrical SOR 01.06.2020)	80000.00	L-S	R
10	NON SOR ITEM Providing & fixing of Steel Bench Area 1.20x0.70 m Height 0.45 m above level seating ----- proper grip fixing with 1:2:4 Cement Concrete	3.00	Each	
11	NON SOR ITEM Mural Wall Art Painting.	600.00	Sqft	
12	NON SOR ITEM Supply installation & fixing of Neon LED GLOW SIGN BOARD written as. 1. I LOVE KHURSIPAR	1.00	Each	

Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer
Municipal Corporation
Bhilai