


MUNICIPAL CORPORATION OF BHILAI NIT

वर्ड क्र. 51 शहीद वीर नारायण सिंह नगर शिशु पार्क के समीप भवन के उपर प्रथम तल एवं मंच निर्माण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020)

| SN | PARTICULARS OF ITEMS | QTY. | UNIT |
|-----|---|---------|------|
| 1 | Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead. | 5.58 | Cum |
| 2 | Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar. | 19.68 | Cum |
| 3 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils. | 44.63 | Cum |
| 4 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size). | 5.42 | Cum |
| 5 | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 17.11 | Cum |
| 6 | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). +Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth: | 22.84 | Cum |
| 7 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars | 3995.00 | Kg |
| 8 | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: | | |
| (A) | Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level. | 41.94 | Sqm |
| (B) | Columns, Pillars, Piers and likes- rectangular or square in shape | 65.20 | Sqm |
| (C) | Beams, lintels, cantilevers & walls | 31.20 | Sqm |
| (D) | Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ) | 127.49 | Sqm |
| 13 | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete. | 27.83 | Cum |
| 14 | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) | 5.23 | Cum |
| 15 | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) (+) Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth: | 21.98 | Cum |
| 16 | Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand) | 153.95 | Sqm |
| 17 | Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand) | 128.70 | Sqm |
| 18 | Providing and making 15mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand) | 123.42 | Sqm |
| 19 | Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. | 94.30 | Sqm |
| 20 | Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. | 268.20 | Kg |

| SN | PARTICULERS OF ITEMS | QTY. | UNIT |
|----|---|----------|------|
| 21 | Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer. | 207.00 | Kg |
| 22 | Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) | 123.42 | Sqm |
| 23 | Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. On new work (two or more coats) | 272.75 | Sqm |
| 24 | Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint | 32.94 | Sqm |
| 25 | Add Extra For Electrification | 26041.00 | LS |



Executive Engineer
Municipal Corporation
Bhilai



Assistant Engineer
Municipal Corporation
Bhilai



Sub-Engineer
Municipal Corporation
Bhilai