(4)

NAGAR NIGAM BHILAI
NIT
वार्ड क्र.–22 कुरूद शासकीय प्राथमिक शाला (22100715201) के भवन का संधारण कार्य।

AS PER PWD BUILDING S.O.R 01.01.2015 & ELECTRICAL S.O.R. 01.06.2020

S.NO	PARTICULAR	QTY	UNIT
1	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less.. including grouting the joints with white cement and matching pigments etc. complete.		
		36.80	sqm
2	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades .. @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.		
	Size upto 200x300mm	33.60	sqm
3	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:		
	Cement Mortar 1:6 (1 cement : 6 coarse sand)	7.20	cum
4	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:		
	In Cement Mortar 1:6 (1 cement : 6 fine sand)	103.20	sqm
5	Painting exterior surface with SMOOTH exterior emulsion paint of manufacturerd with cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with: On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)		
		324.00	sqm
6	Wall painting with acrylic premium emulsion (plastic) manufactured with the cow dung processing emulsion paint of required shade to given an even shade. On old work (one or more coats)		
		324.00	sqm
7	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of .. and corners, all necessary fittings complete includi g applying a priming coat of red oxide zinc chromate primer		
		330.75	kg
8	Painting on old work (one or more coats) to give an even shade with:		
	Premium synthetic enamel paint	46.56	sqm

ASSTT.ENGINEER
Nagar Palik Nigam, Bhilai

SUB ENGINEER
Nagar Palik Nigam, Bhilai