


# MUNICIPAL CORPORATION BHILAI (C.G.)

## NIT


कार्य का नाम :- वार्ड-18 पांच रास्ता स्थित सामाजिक भवन का मरम्मत एवं पानी टंकी लगाने के संबंध में।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.	35.75	Sqm
2	Providing and applying for old work or existing old putty surface 1mm thick ready mix exterior grade putty (manufactured with cow dung processing) on walls to make the surface smooth and even.	71.50	Sqm
3	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	71.50	Sqm
4	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)	71.50	Sqm
5	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	71.50	Sqm
6	Wall painting with premium emulsion ( Plastic) manufactured with the cow dung processing emulsion paint of required shade to give an even shade. On new work (two or more coats)	100.00	Sqm
7	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with the cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with: On old work ( One or more coats applied @ 0.83 ltr/10 sqm)	95.00	Sqm
8	Painting on old work (one or more coats) to give an even shade with: Satin synthetic enamel paint	50.00	Sqm
9	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	Litre
10	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	30.00	Sqm
11	Add 10.00% For Electrification Work (As Per SOR 01.06.2020)	9108.00	Rs

  
**Executive Engineer**  
Municipal Corporation  
Bhilai (C.G)

**Asstt. Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Sub. Engineer**  
Municipal Corporation  
Bhilai (C.G)