

## MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- राष्ट्रीय आपदा मोचन बल तृतीय बटालियन भवन में आवश्यक व्यवस्था हेतु कार्य। (वार्ड क्रमांक 36)

(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.06.2020)

	(As Per PWD Building SOR 01.01.2015 & Electric SOR 0						
S.N.	PARTICULERS OF ITEMS	Quantity	UOM				
1	Exeavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	39.29	Cum				
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	9.02	Cum				
3	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	53.6	Sqm				
(B)	Columns, Pillars, Piers and likes- rectangular or square in shape	55.92	Sqm				
(C)	Beams, lintels, cantilevers & walls	30.08	Sqm				
(D)	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	50.11	Sqm				
4	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.  1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	25.94	Cum				
5	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	13.4	Cum				
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars	2593.92	Kg				
7	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:  Cement Mortar 1:6 (1 cement : 6 coarse sand)	2.1	Cum				
8	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering.	52.77	Cum				
9	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form	0.44	Cum				
10	Applying a coat of hot bitumen VG-10 using @ 1.7kg/ sqm on damp proof course after cleaning the surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil.	8.88	Sqm				
11	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	22,71	Cum				
12	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	22.71	Cum				
13	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	162.47	Sqm				



S.N.	PARTICULERS OF ITEMS	Quantity	UOM
14	Providing and making 15mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5	122.13	Sqm
	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4	45.86	Sqm
16	Providing and fixing ceramic glazed wall tiles conforming to IS: 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.  Size above 200x300mm	93	Sqm
17	Providing and laying ceramic glazed floor tiles conforming to IS: 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size above 300x300mm	59.42	Sqn
18	Providing and fixing 30mm thick fibreglass reinforced plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF) / Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table - 3 of IS: 14856: 2000, complete.	19.74	Sqm
19	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	3087	Kg
20	Painting on new work (two or more coats) to give an even shade with:  Satin synthetic enamel paint	220.5	Sqn
21	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	330.46	Sqm
22	On new work (two or more coats)	208.33	Sqm
23	On new work (Two or more coats applied @ 1.43 hr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)		Sqm
24	White Orissa pattern W.C. pan of size 580x 110 mm	10.00	Eacl
25	and overflow pipes but without littings and the base support for tank	2000	Litr
26	required : White Size 550x450 mm	3.00	Eacl
27	Providing and fixing flexible P.V.C. waste pipe to sink or wash basin including P.V.C. waste fittings complete. 32 mm dia	3.00	Each



5-	PARTICULERS OF ITEMS	Quantity	UOM
28	Providing and constructing brick masonry road gully chamber 50x45x60 cm with well burnt modular clay bricks crushing strength not less than 35kg/cm2 in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450 mm precast R.C.C. horizontal grating with frame complete as per standard design.		Each
30	Providing and laying in trenches G.l. pipes medium class complete with G.l. fittings including excavation of trenches, refilling the same and testing of joints complete:25 mm dia. nominal bore	100	Meter
31	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete: 15 mm dia. nominal bore	50	Meter
32	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete:25 mm dia. nominal bore	50	Meter
33	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm nominal bore.	6	Each
34	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality and weighting not less than 350 grams): Bib cock	20	Each
35	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS: 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion etc complete. 150 mm dia pipe.	25	Meter
36	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.25	Cum
36	Supplying, installation, testing and commissiong of following size drinking water cooler storage type ISI marked, eco friendly non CFC refrigarant, water tank and cooler cabinet sheet material-stainless steel {grade AISI 304} with thickness>= 0.8 mm, with PUF insulation including all accessories connection etc complete as per specification. 150/300 Ltrs/hr	ı	Nos
37	ADD EXTRA FOR ELECTRIFICATION Lum Sum		

कार्यशस्त्र अभियन्ता नगर पातिक निगम, मिलाई

सहायक अभियन्ता नगर पालिक निगम, मिलाई