


3


## MUNICIPAL CORPORATION BHILAI NIT

कार्य का नाम:- वार्ड क्रमांक 34 वीर शिवाजी नगर शिव शक्ति कॉलोनी सुभाष आटा चक्की के पास एवं अदरश अस्पताल के पास पुलिया संधारण कार्य।

BUILDING SCR 2015

| S.NO. | Item no | PARTICULARS OF ITEMS   | QUANTITY | UNIT |
|-------|---------|--|----------|------|
| 1     | 16.43.2 | Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix   | 45.00    | Cum  |
| 2     | 1.26.3  | Carriage by mechanical transport upto 5 km lead: Dismantled Building debris (Mulba)  | 45.00    | Cum  |
| 3     | 1.1.1   | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.<br>In all types of soils.           | 90.00    | Cum  |
| 4     | 1.26.1  | Carriage by mechanical transport upto 5 km lead: Earth   | 90.00    | Cum  |
| 5     | 3.1.2   | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).  | 6.00     | Cum  |
| 6     |         | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).  | 4.80     | Cum  |
| 7     | 3.2.1   | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).                                       | 36.00    | Cum  |
| 8     | 3.12.1  | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415                                   | 2160.00  | Kg   |
| 9     | 2.1.1   | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level. | 270.00   | Sqm  |

  
कार्यपालक अभियन्ता  
नगर पालिक निगम, गिलाई

  
सहायक अभियन्ता  
नगर पालिक निगम, गिलाई

  
उप अभियन्ता  
नगर पालिक निगम, गिलाई